


BOQ FOR REPAIRING OF DRAIN IN THE NEW ADMINISTRATIVE BUILDING

SI No	Description	Qty	Unit	Rate in Figure	Rate in Words	Amount (in Rs)
1	Desiltation of the existing drain	1	Job			
2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.					
	Nominal concrete 1:4:8 or leaner mix (i/c equivalent design mix)					
	Total=	4.03	cum			
3	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.					
	Total=	14.31	cum			
4	Clearing grass and removal of the rubbish up to a distance of 50 m outside the periphery of the area cleared.	48.00	sqm			
5	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.					
	Total=	16.71	cum			
6	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in- Charge:					
	All kinds of soil					
	Total=	15.25	sqm			
7	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.					
	Thermo-Mechanically Treated bars of grade Fe-500D or more					
	Total=	464.75	kg			
8	Centering and shuttering including strutting, ropping etc. and removal of form for					
	Foundations, footings, bases of columns, etc. for mass concrete					
	Total=	27.30	sqm			





BOQ FOR REPAIRING OF DRAIN IN THE NEW ADMINISTRATIVE BUILDING

SI No	Description	Qty	Unit	Rate in Figure	Rate in Words	Amount (in Rs)
9	Lintels, beams, plinth beams, girders, bressumers and cantilevers					
	Tie Beam	65.00	sqm			
	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :					
10	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)					
	Tie Beam	5.85	cum			
11	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 In foundation and plinth in:					
	Cement mortar 1:4 (1 cement : 4 coarse sand)					
	BW in the drain	16.25	cum			
12	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in :					
	Cement mortar 1:3 (1 cement : 3 coarse sand)					
	In the connecting darins	10.00	sqm			
13	12 mm cement plaster finished with a floating coat of neat cement of mix :					
	1:4 (1 cement: 4 fine sand)					
	Total=	97.25	sqm			
14	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
	1:1½:3 (1 Cement: 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)					
	Total=	6.33	cum			
14	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings This includes jointing of pipes & fittings with one step CPVC solvent cement, trenching, refilling & testing of joints complete as per direction of Engineer in Charge.					

gurel

[Signature]

[Signature]

BOQ FOR REPAIRING OF DRAIN IN THE NEW ADMINISTRATIVE BUILDING

SI No	Description	Qty	Unit	Rate in Figure	Rate in Words	Amount (in Rs)
	External work					
	100 mm nominal dia Pipes	2.10	metre			
15	Providing, fitting of 900 mm 4 Nos of RCC Ring well with 900mm RCC cover	1.00	Job			
Total						

Rupees Only

Sealed Signature of the Tenderer

Handwritten signatures in blue ink:
 1. A signature that appears to be "Jwel" with an arrow pointing to the left.
 2. A checkmark-like signature.
 3. A signature that appears to be "Ay" or similar.