

BOQ for Installation of switch boards & pedestal fans at the office of Academic Registrar, Engineering Cell of Administrative Building, Cotton University

SL. NO.	ITEM DESCRIPTION	UNIT	QNTY	RATE in Figure	RATE in Words	AMOUNT
1	Wiring for circuit/ submain wiring alongwith earth wire with the following sizes of FRLS PVC insulated copper conductor, single core cable in surface/ recessed medium class PVC conduit as required.					
	2 X 2.5 sq. mm + 1 X 2.5 sq. mm earth wire	Mtr	65			
	2 X 4 sq. mm + 1 X 4 sq. mm earth wire	Mtr	35			
2	Supplying and fixing following modular switch/ socket on the existing modular plate & switch box including connections but excluding modular plate etc. as required.					
	15/16 A switch	Each	32			
	6 pin 15/16 A socket outlet	Each	32			
3	Supplying and fixing following size/ modules, GI box alongwith modular base & cover plate for modular switches in recess etc. as required.					
	8 Module (125mmX125mm)	Each	10			
	4 Module (125mmX75mm)	Each	2			
4	Supply, fitting, fixing of pedestal fans as approved and directed by the deptt. Make- Orient Model- 400 mm Stand 32 Signal White	Each	1			
5	Supply, fitting, fixing of 1400mm ceiling fans as approved and directed by the deptt. Make- Orient Model- Summercool	Each	4			
Total in Rs.						

Rupees Only

Sealed Signature of the Tenderer