

Price Bid

BOQ for Construction of Panelling Works in the office of Vice Chancellor, Cotton University(Package-B)						
Sl No	Description	Unit	Qty	Rate in Figure	Rate in Words	Amount (in Rs)
1	Providing, Fixing and Finishing 12mm / 19mm / 6mm Plyboard Panelling of required thickness fixed over brick wall / Sal Wood Frame of size 50mm x 38mm & 50mm x 50mm made of required section as per design finished with 1mm Laminate as specified, complete with necessary hardwares and fittings as specified and directed.	Sq.M.	56.06			
Total						
Rupees (in words)						




Sealed Signature of the Tenderer
Date