

PRICE BID						
SI No	Description of Work	Unit	Qty	Rate	Rate in Words (Rs)	Amount (Rs)
DSR-2021 Item - 2.8.1	Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, lift upto 1.5 m, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	cum	24.04			
DSR-2021 Item -2.22.1	Surface dressing of the ground including removing vegetation and inequalities not exceeding 15cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.50 m.	sqm	330			
DSR-2021 Item -2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	cum	16.28			
DSR-2021 Item 11 ?	Dry brick on edge flooring in required pattern with bricks of class designation 7.5 on a bed of 12 mm mud mortar, including filling joints with jamuna sand. with common burnt clay non modular bricks.	sqm	21.43			
DSR-2021 Item -4.1.5	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	1.411			
DSR-2021 Item -5.1.2	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level : 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	23.71			
DSR-2021 Item -5.22.6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	kg	600			
DSR-2021 Item -4.3.1	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns.	sqm	9.25			
DSR-2021 Item -4.3.3	Centering and shuttering including strutting, propping etc. and removal of form work for : Columns, piers, abutments, pillars, posts and struts.	sqm	64.935			
DSR-2021 Item -6.1.2	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand)	cum	1.688			
DSR-2021 Item -6.12.2	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundations and plinth in : cement mortar 1:4 (1 cement : 4 coarse sand)	sqm	65.25			

4

HA

DSR-2021 Item -13.2.1	15 mm cement plaster on the rough side of single or half brick wall of mix : 1:4 (1 cement: 4 fine sand)	sqm	183.4			
DSR-2021 Item -13.44.1	Finishing walls with water proofing cement paint of required shade : New work (Two or more coats applied @ 3.84 kg/10 sqm)	sqm	183.4			
DSR-2021 Item -10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	kg	87			
DSR-2021 Item -16.16	Supplying and fixing turn buckles and straining bolts for barbed wire fencing.	Each	16			
DSR-2021 Item -16.18.1	Fencing with angle iron post placed at required distance embedded in cement concrete blocks, every 15th post, last but one end post and corner post shall be strutted on both sides and end post on one side only and provided with horizontal lines and two diagonals interwoven with horizontal wires, of barbed wire weighing 9.38 kg per 100 m (minimum), between the two posts fitted and fixed with G.I. staples, turn buckles etc. complete. (Cost of posts, struts, earthwork and concrete work to be paid for separately). Payment to be made per metre cost of total length of barbed wire used.---With G.I. barbed wire	M	200			
DSR-2021 Item -15.3.6	Dismantling barbed wire or flexible wire rope in fencing including making rolls and stacking within 50 metres lead. (DSR 15.36) - old Wall	M	200			
DSR-2021 Item -	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	cum	13.13			
DSR-2021 Item -15.7.4	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.	cum	11.522			
DSR-2021 Item -2.33.3	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material. - Tree	each	2			
Non DSR Item	Hire and running Charge of Loader & Tipper (Market Rate)	L.S	3 days			
	Amount in Words (Rs)	Total Amount (Rs)				